F.No.S31/100/2019 Pr. Cus.   Dated: 18.05.2019

Sub: Request for quotations – Renovation work of Licence Section (Ministerial) of Custom House, Cochin-9.

* * * * * * * *

On behalf of the President of India, sealed quotations are invited for the below Renovation Work of Room No.42 (Licence Section AO/SC (P) Room) at Custom House, Willingdon Island, Cochin-9.

Sl. No.	Description of the Work
1	Supply and Laying of 60x120cm Vitrified Floor tiles by using thin set Adhesive paste – Total Area 233 Sq.ft.
2	Supply and painting of the Wall – Removing old paint with sand paper, One Coat Cement Primer and Two Coat Emulsion (Patch Work Where ever necessary) – Total Area 746 Sq.ft.
3	Ceiling Work with gagged PVC Sheet – Total Area 217 Sq.ft.
4	**Interior Work** – Making of Cubicles : a) Back side rack with 4 section using 18mm laminated MDF sheet – 68 Sq.ft b) Making of Front Table with 3 section using 18 mm laminated MDF sheet – 32 Sq.ft. c) Cubicle 2 partition 4 mm plywood section covering with Laminated MDF sheet – 78 Sq.ft. d) Making side table with 3 section using 18 mm laminated MDF sheet – 26 Sq.ft.

You are requested to inspect the site and submit your quote for the above work on or before 3.00pm ~~pm~~ on 27.05.2019 to the Commissioner of Customs, Cochin.

Yours faithfully,

(V Usha)
Superintendent of Customs (Prev.)

Copy submitted to:
1. The Commissioner of Customs, Custom House, Cochin.
2. The Superintendent of Customs, EDI Section
3. Notice Board.